J. R. SCHNEIDER CONSTRUCTION, INC.

Page 1

PROPOSAL

March 7, 2018

1315 W. 9th Street

Plans by: Perales (2/9/17)

Addenda Seen: 0

We propose to provide labor, materials, equipment and supervision necessary for:

- Clear and dispose of trees.

\$ 2,000.00

- Building Pads – Excavate and grade to 14" below FFL for 6" slab and 8" void forms. Dispose of unused spoils.

\$ 43,000.00

**ADD - for 6" base, all-weather working surface.

\$ 4,200.00

- Concrete Paving Area – Excavate and grade. Compact and moisture condition existing subgrade for concrete paving. Dispose of unused spoils.

\$ 25,500.00

- Landscape Areas – Excavate and rough grade. Backfill curbs to 4" below finish grade using onsite soil. Dispose of unused spoils.

\$ 7,500.00

- Not Included: permits, fees, testing, initial survey/control points, structural excavation or backfill, vapor barriers or sand cushions, gravel drainage layers, pond work, topsoil or fine grading for landscaping, grassing or re-seeding, concrete work, safety barrier/fence, hazardous material handling, move or remove existing utilities, barricades, traffic control, car stops, signage, striping, other contractors spoil disposal, demolition of existing structures, **shoring, bracing, not responsible for damage of existing retaining wall on east side of property, wall backfill,** lime stabilization, water to restore vegetation, temporary fire lane access, work in areas not shown to have new grading.
- Price valid for 30 days
- These prices are base on given information. Verification of existing grades is required prior to beginning contract
- We require at least one complete set of drawings, four control points, one bench mark and related CAD file for survey and layout purposes.
- Prices based on Civil and Structural drawings only.
- Water for construction to be provided by GC or owner.

Submitted by: Decker Basham

(512) 963-4572 (mobile) Email: Dbasham@jrsatx.com